

**Work Requirements for proposed Sewerage System of Package 2A in Hospet Town under ADB assisted NKUSIP.**

1) Providing & laying of sewer pipe line of length 176 km with varying diameters from 150 mm dia to 900 mm dia of stoneware pipe and RCC pipes as follows.

<b>Sl No</b>	<b>Diameter of pipe</b>	<b>Material</b>	<b>Length in meter</b>
1	150mm	Stoneware	150502.90
2	200mm	--Do--	5783.00
3	250mm	--Do--	4629.00
4	300mm	RCC NP3	4396.70
5	450mm	--Do--	5868.00
6	600mm	--Do--	3178.80
7	750mm	--Do--	1078.10
8	900mm	--Do--	245.70
		<b>Total</b>	<b>175682.20</b>

2) Construction of 1.75 Km RCC secondary drains of different sizes as follows

i)1.25X1.5meter

ii)1.5X1.7meter

iii)2.5X1.70meter

3) Construction of 4 nos. RCC box culverts.